



**CHABOT- LAS POSITAS
COMMUNITY COLLEGE DISTRICT**
Facilities Planning & Management Department

September 24, 2008

**Addendum No. 3
INVITATION FOR BID NO.: 08-12
Information Technology Building- Las Positas College**

All Prospective Bidders:

This Addendum modifies the original Bid Documents for the above Bid. Acknowledge receipt of this addendum in the space provided on the BID PROPOSAL FORM. Failure to do so may subject Bidder to disqualification.

The original Bid Documents are modified by the revision as follows:

See attached Addendum No. 3 description and drawings.

If you have any questions regarding this Addendum No.3 please contact the Office of the Facilities Planning & Management in **writing, via facsimile or email**. All other terms and conditions of BID No. 08-12 to remain the same.

Regards,

Victoria L. Lamica
Contracts Manager
vlamica@clpced.org

C: Bid File

- Item (6) Refer to Pre-Bid RFI #18:
a. SEE ATTACHED for response.
- Item (7) Refer to Pre-Bid RFI #19:
a. SEE ATTACHED for response.
- Item (8) Refer to Pre-Bid RFI #20:
a. SEE ATTACHED for response.
- Item (9) Refer to Pre-Bid RFI #21:
b. SEE ATTACHED for response.
- Item (10) Refer to Pre-Bid RFI #22:
a. SEE ATTACHED for response.
- Item (11) Refer to Pre-Bid RFI #23:
a. SEE ATTACHED for response.
- Item (12) Refer to Pre-Bid RFI #24:
a. SEE ATTACHED for response.
- Item (13) Refer to Pre-Bid RFI #25:
a. SEE ATTACHED for response.
- Item (14) Refer to Pre-Bid RFI #26:
a. SEE ATTACHED for response.
- Item (15) Refer to Section 01062, EIR / Biological Opinion Compliance:
a. **ADD** a paragraph at the end of 2.01 Biologist to read:
"The following firms have been approved by US Fish and Wildlife Services to provide Biological Consulting Services on this project.
HT Harvey
Steve Rottenborn
3150 Almaden Expressway #145
San Jose, CA 95118
(408) 448-9450
srottenborn@harveyecology.com
- Kleinfelder, Inc.
Bill Goggin
Project Biologist
365 Victor Street, Suite L
Salinas, CA 93907
831-755-7900 (o)
WGoggin@kleinfelder.com"
- Item (16) Refer to Section 02750, Site Concrete:
a. **OMIT** paragraph 2.5., Fiber reinforcement in its entirety.
b. **OMIT** paragraph 3.6.J.1., in its entirety.
- Item (17) Refer to Section 16810:
a. **REVISE** paragraphs 2.01, 2.02, 2.03, 2.04, and 2.05 to read:
"PART 2 – PRODUCTS
2.01 CONTRACTOR PROVIDED PRODUCTS

- A. SP Controls Pixie Control Panel: #PX2-MP-IR
- B. Tannoy Ceiling Speakers: CMS 501
- C. Projector Mount: Chief #RPA-XXX (To Fit OFCI Projector)
- D. Projector Support Kit: Chief CMA 440
 - 1. Extension Column: Chief #CMA-003 or as required.
- E. 120" Diagonal (72"H"x96"W) Electric Projector Screen:
 - 1. Dalite-Advantage Electrol With Built In RS232 Control
- F. Wall Interface Panel:
 - 1. Extron AAP 104
 - 2. Extron AAP Plate #70-404-11
 - 3. Extron AAP Plate #70-091-12
 - 4. Extron AAP Plate #70-107-11
 - 5. Extron AAP Plate #70-096-11
 - 6. Extron AAP Plate #70-329-11
 - 7. Extron AAP Plate #70-636-02
 - 8. Extron AAP Plate #70-090-11
- G. Floor Box Interface Panel:
 - 1. Extron CPM 121
 - 2. Extron MAAP Plate #70-309-14
 - 3. Extron MAAP Plate #70-293-13
 - 4. Extron MAAP Plate #70-315-11

2.02 CABLE

- A. Contractor must provide all cables and connectors from the Interface panels, to the projectors and speakers.
- B. Contractor must provide all cables and connectors from the Switcher Preamp to interface connectors.
- C. Contractor must provide audio and video cable from the VCR/DVD player to the Switcher Preamp.
- D. Contractor must provide audio cable from the Switcher Preamp to the audio amplifier.
- E. Contractor must provide all control cables and IR Emmiters.
- F. Contractor shall provide all Misc. patch cables for a fully operational system.
- G. Projector Video Cable:
 - 1. VGA Video: Extron MHR-5P #22-103-0x
(As Req)
 - 2. Component Video: RG59-3 coax-Belden 1824A
(As Req)

3. "S" Video: Extron MHR-2P #22-123-0x
(As Req)
4. Composite Video: RG59 Series: Extron 22-146-0x
(As Req)
5. Connectors
(As Req)
- H. Control Cable: Belden 88641
(As Req)
 1. SP Controls IR Emitters
(As Req.)
 2. Connectors
(As Req.)
- I. Audio Cable, 18 awg.: West Penn 25293B
(As Req)
- J. Misc. Patch Cables As Required For Patching in AV Cabinet
(As Req)

2.03 OWNER FURNISHED CONTRACTOR INSTALLED PRODUCTS

- A. Mobile Cabinet shall be a 12U wood cabinet with front and rear doors. The front door shall be plexiglass. The cabinet shall be 28.625"Hx22"Wx25"D, 3" castors, 19" rack rails, Cooling Fan and locking doors.
 1. Preferred product will be a Dalite 12U Equipment Rack
- B. Video Projector: Ask Proxima C450 or equal.
 1. Spare Lamp: Appropriate replacement for projector.
- C. SP Controls Preamp Switcher: SP3-AFVP+
- D. Distribution Amplifier: Extron P/2 DA2xi
- E. DVD/VHS Combo: Panasonic DMR-EZ48VK or equal

2.04 POWER

- A. The electrical contractor will provide an electrical outlet at the projector location.
- B. The electrical contractor will provide an electrical outlet for equipment in the wall for the mobile AV cabinet.
- C. The electrical contractor will provide power to the projection screen.

2.05 ENCLOSURES AND PATHWAYS

- A. Use mounting hardware and anchors recommended by the Manufacture of any material that shall be mounted to the building or structure.

- B. The Contractor shall select the appropriate mounting bracket kits for mounting equipment into racks and input/control panels into walls and furniture.
- C. The Electrical Contractor will provide a cable conduit/pathway to accommodate the following locations:
 - 1. Control Panel to ceiling.
 - 2. Wall Interface Panel to ceiling.
 - 3. Projection Screen Switch to ceiling.
 - 4. AV Floor Box to ceiling."

B. CHANGES AND/OR CLARIFICATIONS TO THE DRAWINGS:

- Item (18) Refer to Sheet A1.11, Site Plan:
 - a. Refer to Addendum No. 2, Item (52)b.:
CORRECTION: OMIT Keynote 145; Keynote 143 to be retained.
 - b. REVISE Site Plan as shown on drawing AD3-A02, SEE ATTACHED.
- Item (19) Refer to Sheet A5.11, Room Finish Schedule:
 - a. **REVISE** Room Finish Schedule as shown on drawing AD3-A01, SEE ATTACHED.

CONFORMANCE WITH CONTRACT DOCUMENTS, PROJECT MANUAL, DRAWINGS AND SPECIFICATIONS

All addenda work shall be in strict conformance with the Contract Documents, Project Manual, Drawings and Specifications as they pertain to work of a similar nature.

BFGC ARCHITECTS PLANNERS INC.

BY: 
DEAN TATSUNO, AIA

